Development of modular composite walls in the RAMSSES project

E-LASS meets MariLight – Seminar on Lightweight Applications at Sea 30.01.2020 Atlantic Hotel Universum, Bremen

Arthur-Hans Thellmann, R&D department Meyer Werft GmbH & Co. KG



Agenda

Meyer Werft – The shipyard and its Products

Lightweight design – WHY

EU-Project RAMSSES

Current Status of WP13

Specifications and Conditions Demonstrators Design Testing

Summary and outlook

2

Shipyard History

1795-1841 | Willm Rolf Meyer founded a timber shipyard 225 years ago

- 1841-1876 | Franz Wilhelm Meyer
- 1872-1920 | Joseph-Lambert Meyer


Pioneering spirit \rightarrow iron ships with steam machines

- 1920-1951 | Franz Joseph Meyer
- 1920-1924 | Bernhard Meyer
- 1951-1977 | Godfried Meyer

Production of first gas tankers

- 1941-1998 | Joseph-Franz Meyer
- 1985 | Launch of the "Homeric",

the shipyard's first cruise ship





MEYER WERFT

MEYER WERFT today

Since 1982 | Bernard Meyer Since 2012 | Dr. Jan Meyer Since 2016 | Tim Meyer Since 2017 | Thomas Weigend











Arthur-Hans Thellmann

Array of products - Ship types



Lightweight design – WHY

Reduction of the ship's weight by using fiber reinforced polymers:

- Less fuel/energy consumption
- Less emissions
- Less draught
- Better stability
- More passengers/payload
- More/heavier attractions on the upper deck
- Reduction of maintenance costs
- Improvements of the design possibilities modern and complex designs are possible
- Functional integration
- Possibilities to react late in the production process to customer wishes
- Lightweight design a design philosophy with increased performance per definition

RAMSSES - Realization and Demonstration of Advanced Material Solutions for Sustainable and Efficient Ships



Arthur-Hans Thellmann

Development of modular composite walls in the RAMSSES project

LCPA

RAMSSES – MW Work Package

Integration of system for internal walls and superstructure of cruise ships into shipyard processes

Close Collaboration with InfraCore Company, SAERTEX and CMT to:

- Develop highly efficient shipyard process for adaptation, assembly and outfitting of a modular system
- Performing numerical and analytical analysis to pass the requirement on the heat insulation, eigenfrequency, deformation, maximum width and weight of the composites wall panels
- Development of a design catalogue for quick assembly and joining technology between steel and composite component for series production
- Assessment of the influence on the production process
- Introduction of FRP material into yard production for cruise ships by building onshore and onboard demonstrator



Specifications and Conditions

FRP Interim Guidelines were approved by MSC 98 in summer 2017

➤ consistent approach is taken with regard to standards of fire safety of ships

➤ the level of fire safety afforded by the provisions of SOLAS chapter II-2 is maintained

➢Guidelines on alternative design and arrangements for fire safety (MSC/Circ.1002, as amended by MSC.1/Circ.1552)

> use of performance-based methods – "equivalence principle"

➤4 years of time to use this guideline AND provide good, working examples to SDC / MSC





4 ALBERT EMBANKMENT

Ε

9

Specifications and Conditions


Technical properties:

- Accelerations up to 1.5 g
- Fire behavior: 2010 FTP Code Part 2, 5, 10, 11
- Durability against the environment: temperature range -40°C to +80°C and humidity of 95%
- UV and salt water resistant
- Heat / sound insulation and vibration / loadings acc. Ships specification
- Robustness reg. storage and transportation
- Various types of connections, all must provide fire safety properties and no "hot work" disconnectability
- Penetrations and modifications on board without harming worker's health and specific equipment
- Free of smell after installation

Demonstrators – On-shore

On shore demonstrator:

- Mock-up to assess requirements, especially the connection to the ship structure
 - Composite wall to deck / ceiling
 - Composite wall to pillar
 - T-joint of composite walls / steel wall
 - Butt joint of composite wall to steel wall
 - Corner connection of composite walls / steel wall





Arthur-Hans Thellmann

Development of modular composite walls in the RAMSSES project

Composite

Door

Demonstrators – On-board


Scope:

- Exchanging non load-bearing steel walls which are not able to affect global strength
- Walls are carrying local loads only
- Composite structure is flexible enough to obey the deformation of the ship hull and to bear these deformations

Typical structures are walls of:

- Stores
- Galley / pantry
- Cold rooms
- Technical rooms
- Restrooms
- Superstructures





> Estimation of a cruise ship with 145.000GT \rightarrow 6800m² per ship exchangeable

Design concept

Design:

- Modular concept to be able to exchange at least 80% of these walls in a serial production with high potential of standardization
- Standardized & easily to be mounted on-board of the vessel even at a very late stage of production




Design concept

- Laminate consists of Glass-NCF with Epoxy resin, foam core reinforced by InfraCore Technology and a cork layer
- LEO intumescent layer as the outer protection layer
- Dimensions to ensure late assembly on board (2 persons handling)







Testing

Mechanical testing (IFAM):

- Density, Reinforcement content & Glass transition temperature
- Tensile, Compression, ILSS & Shear
- 80 tests are planned
- Specimen produced and will be tested Jan/Feb 2020
- Fire testing (RISE)
 - ISO 5660-1, cone calorimeter, screening for FRM-test
 - promising values achieved for Part10
 - •Part 2, smoke and toxicity
 - HF, HCL, HBr, HCN, Nox, SO2 all OK, but too high values for smoke density Dm and CO
 - Part 5, spread of flame
 - Qsb, CFE & Qp all OK, but Qt value too high
 - Part 10, FRM-test
 - Flashover at 16:35 min
 - Small-scale furnace test, screening for FRD -> Feb. 2020
 - Part 11, FRD-test -> Feb. 2020
- N&V testing (RISE) -> March 2020










Arthur-Hans Thellmann

Impressions Part 10



Arthur-Hans Thellmann

Impressions Part 10



Arthur-Hans Thellmann

Development of modular composite walls in the RAMSSES project

30/01/2020

Summary and outlook

- Design concept & Assembly process is finished
- Assembly process trialed within Part10 test
 - > Panels for On-shore Mock-up in production and will finalize open issues
- Testing is taking place at the moment (mech. + fire)
- Good progress of the material combination to fulfill fire testing requirements
- BUT: Material still requires "fine-tuning"
 - Further screening tests to determine final stack-up and combination
- Presentation to the owner (on-shore demonstrator)
- Approval process (AD&A) to be started as soon as all issues are cleared
 - Installation of on-board demonstrator

THANK YOU FOR YOUR ATTENTION



MEYER WERFT GmbH & Co. KG Industriegebiet Sued 26871 PAPENBURG GERMANY

Copyright MEYER WERFT GmbH & Co. KG, Papenburg, Germany. All rights reserved. This document is the sole intellectual property of MEYER WERFT GmbH & Co. KG and shall not be brought to the knowledge of any third parties neither in original nor by any reproduction and in each case neither as a whole nor in parts without the prior written consent of MEYER WERFT GmbH & Co. KG.